

CENTRAL INSTITUTE OF MINING & FUEL RESEARCH. DHANBAD  
(Council of Scientific & Industrial Research)

NOTICE INVITING TENDER  
(*Displaying in Notice Boards*)

No. 23(278)2007-GA/

Dated : 03/09/2007

Sealed tenders are hereby invited from bonafide govt. contractors, registered with CPWD, State, PWD, MES, Post and Telegraphs, Railway, Defence and other Govt. Department, CSI R or any of its laboratories, who have successfully completed at least 3 (three) similar type (equal to 40% of the estimated value) or 2 (two) similar type (equal to 50% of the estimated value) or 1 (one) similar type (equal to 80% of the estimated value) in last (5) five years.

Sl.	Description of work	Estimated Amount (Rs.)	Earnest money	Time of completion	Cost of Tender Documents
1.	Renovation of small overhead reservoir at CIMFR Colony	78,802=00	1,576=00	20 days	150=00

The following proof of documents in original or duly attested to be produced at the time of issuing tender paper and also to be submitted alongwith submission of tender for verification.

1. Latest Income tax clearance certificate
2. Valid Jharkhand Sales Tax, Registration No. and Clearance certificates.
3. Completion certificate along with payment received of three similar works (including schedule) of values as mentioned above from an officer not below the rank of Executive Engineer of the concerned Department.

**Tenders to be submitted in 2 Bid System**

1. Part-I  
(Technical Bid)

Consists of following documents

- a) Proof of documents as mentioned above (1-3)
- b) Earnest Money
- c) Cost of Tender documents (In case of tender document down loading from CIMFR Web site.)

2. Part-II

Consists of following documents

- a) Costing alongwith full specifications of the items involved in the work including all Taxes & Levies as per different laws.

Tender paper will be on sale from 31/08/2007 to 13/09/2007 on payment basis (Non refundable) on all working days of CIMFR up to 3:00 P.M. and will be also available in CIMFR website [www.cmriindia.nic.in](http://www.cmriindia.nic.in) , that can be downloaded for submission. Those parties who submit their tenders after down loading, shall be required to pay the above mentioned amount (*Cost of Tender Documents*) in the form of Account Payee D.D. drawn in favour of Director, CMRI, Dhanbad payable at SBI, Hirapur, alongwith their Technical Bid.

The Part-I & Part-II are to be individually sealed in separate envelopes and are to be put in a 3<sup>rd</sup> envelope which shall also be sealed and superscribed with the name of work in bold letters, address of the depositors and to be dropped in the Tender Box kept in the Office of the Administrative Officer, CIMFR, Dhanbad, after duly signed by him on or before 20/09/2007 at 3:00 P.M. and will be opened on the same day at 3:30 P.M., in presence of the intending tenderers or their authorized representatives whoever present themselves at the time of opening of tenders.

- Ø **IT IS REQUIRED TO SUBMIT THE COST OF TENDER DOCUMENTS ALONG WITH TECHNICAL BID AS MENTIONED ABOVE.**
- Ø **EARNEST MONEY SHOULD BE DEPOSITED IN THE FORM OF ACCOUNT PAYEE DEMAND DRAFT PAYABLE AT SBI, HIRAPUR (CODE-1670) DHANBAD IN FAVOUR OF DIRECTOR, CENTRAL MINING RESEARCH INSTITUTE, DHANBAD.**
- Ø **INCOMPLETE TENDERS, LATE / DELAYED TENDERS AS WELL AS TENDERS WITHOUT EARNEST MONEY SHALL BE SUMMARILY REJECTED.**
- Ø **DIRECTOR, CIMFR, RESERVES THE RIGHT OF ACCEPTING ANY TENDER IN PART OR FULL OR REJECTING ALL WITHOUT ASSIGNING ANY REASON.**

In-Charge (Civil)

Administrative Officer

**CENTRAL MINING RESEARCH INSTITUTE, DHANBDAD**  
(Council of Scientific & Industrial Research)

Name of work : Renovation of small overhead reservoir at CMRI Colony

Sl.	Description of work	Qty.	Per	Rate	Amount
1.	Repairs to plaster of thick 12mm to 20 mm in patches of area 2.5 sqm and under including cutting the patches in proper shape and preparing and plastering the surface of the wall complete including disposal of rubbish to the dumping ground within 50m lead with cement mortar 1:4 (1 Cement : 4 fine sand)	445.00	Sqm		
2.	Applying of neat cement punning work	81.75	Sqm		
3.	Cutting holes upto 0.15 x 0.15m in RCC wall for cutting of unwanted tree plant on RCC wall and repairing the hole after insertion of hole in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including finishing complete work	6 Nos.	Each		
4.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc. complete.				
a)	50 mm thick with 20 mm nominal size stone aggregate	41.00	Sqm		
b)	40 mm thick with 20 mm nominal size stone aggregate	58.00	Sqm		
5.	Providing and laying of flat brick soling in bed sand 2 mm thick with jointing etc.	58.00	Sqm		

6.	Extra for providing and mixing water proofing material in cement concrete work @ 1 kg per 50 kg of cement	50.00	Kg		
7.	Finishing walls with water proofing cement paint "Snowcem-Plus" of M/s Snowcem India Ltd. Or equivalent of required shade : New work (two or more coats applied @ 3.84 kg/10 Sqm)	445.00	Sqm		
8.	Extra for washed grit plaster on exterior walls of height more than 10m ground level for every additional height of 3.00 m or part thereof etc.	445.00	Sqm		
9.	Dismantling old plaster or skirting racking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 m lead.	445.00	Sqm		
10.	Demolishing cement concrete including disposal of material with 50 m lead of 1:2:4 etc. mix.	2.00	Cum		