

CENTRAL INSTITUTE OF MINING & FUEL RESEARCH, DHANBAD
(Council of Scientific & Industrial Research)

CORRIGENDUM

With reference to CIMFR tender notice vide no. 23(367,368,369,370)/09-GA & QP/GE/01/Civil/P-06/2009-10/87, dated: 29/04/2009 displayed in CIMFR notice board as well as in the notice board of ISM, PWD, CPWD, CIMFR Digwadih & BIT Sindri, and also published on following news papers on dated 01/05/2009 1) The Telegraph, Kolkata Publication (English daily), 2) Times of India, New Delhi Publication (English National) & 3)Hindustan, Dhanbad Edition (Hindi Local). The last date for selling of the tender documents for **sl. no. 1** may be read as 12/06/2009. The last date for submission of tender document may read as 15/06/2009, 3.00 P.M. Tender will be opened on the same day 3.30 P.M. Website no. www.cimfr.nic.in. The remaining conditions of NIT will remain same.

CENTRAL INSTITUTE OF MINING & FUEL RESEARCH, DHANBAD

(Council of Scientific & Industrial Research)

Barwa Road, Dhanbad- 826 015 (Jharkhand) INDIA

CIVIL ENGINEERING SECTION

Tenders Documents

for

Execution of

Renovation of I T Centre, Security officer room, room no. 26, 36, 46, 65, 76, 81, 86 at Main building, Library, Ventilation division (TF-5), Calibration cell by providing and fixing of false ceiling, aluminium partition, working table.

In

CIMFR Dhanbad.

INDEX

SECTION	PARTICULARS	PAGE NO.
I	NOTICE INVITING TENDER	2
II	COMMERCIAL BID	3 - 6
III	INSTRUCTION TO BIDDER	20 - 22

NIT NO.:

Phone: 0091-326-2296023/; Fax : 0091-326-229-6025

CENTRAL INSTITUTE OF MINING & FUEL RESEARCH, DHANBAD
(Council of Scientific & Industrial Research)
NOTICE INVITING TENDER

No. 23(367, 368, 369, 370)/2009-GA & QP/GE/01/Civ/P-06/09-10/

Dated: /04/2009

Sealed tenders are hereby invited from bonafide govt. contractors, registered with CPWD, State, PWD, MES, Post and Telegraphs, Railway, Defence and other Govt. Department, CSIR or any of its laboratories, who have successfully completed at least 3 (three) similar type (equal to 40% of the estimated value) or 2 (two) similar type (equal to 50% of the estimated value) or 1 (one) similar type (equal to 80% of the estimated value) in last (5) five years.

Sl.	Description of work	Estimated cost	Earnest money	Time of completion	Cost of Tender Documents
1.	Renovation of IT Centre, Security officer room, room no. 26, 36, 46, 65, 76, 81, 86 at Main building, Library, Ventilation division (TF-5), Calibration cell by providing and fixing of false ceiling, aluminium partition, working table.	21,08,454=20	42,170=00	4 Months	500=00
2.	Exterior treatment of Staff qtrs. type-I, II, III, IV (Except IV/25 to 32) and Girls Hostel at CIMFR HQ, Barwa Road, Dhanbad.	11,47,694=73	22,955=00	4 Months	500=00
3.	Interior and exterior maintenance along with sanitary, water supply fitting & drainage work at DJH CIMFR (HQ), Dhanbad.	3,50,395=25	7,010=00	45 Days	500=00
4.	Repairing work of CIMFR, Dhanbad at staff qtrs. no. IV/32, V/6, IV/46, 36, 10, III/1, 38, 26C, 21, 20, II/50A, 49B, 48A, 46C, 37, 36, 34, 32, 11, I/30, 24, 10, 8, 2, 1, II/46A, 26, I/19, II/9, SA-II/40, II/2, Electrical (M) Sec., Security Sec., Sub-Post Office, Community Girls Hostel, IV/33, 45	3,58,032=35	7,161=00	45 Days	500=00
5	Renovation of Combustion Section at CIMFR Digwadih Campus	2,08,110=00	4165=00	45 Days	500=00

The following proof of documents in original or duly attested to be produced at the time of issuing tender paper and also to be submitted alongwith submission of tender for verification.

1. Valid sales tax, Registration no. & Clearance certificate.
2. Completion certificate alongwith payment received of the similar works (including schedule) of values as mentioned above from an officer not below the rank of Executive Engineer of the concerned Department.

Tenders to be submitted in 2 Bid System

1. Part-I

(Techno-Commercial Bid)

Consists of following documents

- a) Proof of documents as mentioned above (1-2)
- b) Earnest Money
- c) Cost of Tender documents (In case of tender document down loading from CIMFR Web site.)

2. Part-II

(Price Bid)

Consists of following documents

- a) Costing alongwith full specifications of the items involved in the work including all Taxes & Levies as per different laws.

Tender paper will be on sale from 04/05/2009 to 20/05/2009 on payment basis (Non refundable) on all working days of CIMFR up to 3:00 P.M. and will be also available in CIMFR website www.cimfrindia.nic.in, that can be downloaded for submission. Those parties who submit their tenders after down loading, shall be required to pay the above mentioned amount (Cost of Tender Documents) in form of Account Payee D.D. drawn in favour of Director, CIMFR, Dhanbad payable at SBI, Hirapur, alongwith their Technical Bid.

The Part-I & Part-II are to be individually sealed in separate envelopes and are to be put in a 3rd envelope which shall also be sealed and superscribed with the name of work in bold letters, address of the depositors and to be dropped in the Tender Box kept in the Office of the Administrative Officer, CIMFR, Dhanbad, after obtaining date, signature of Administrative Officer / Section Officer on or before 26/05/2009 at 3:00 P.M. and will be opened on the same day at 3:30 P.M., in presence of the intending tenderers or their authorized representatives whoever present themselves at the time of opening of tenders.

For SI no. 5 Tender paper will be available from Civil Engg. Section CIMFR Digwadih Campus and the same will be opened at Administrative Office, CIMFR, Digwadih Campus on the date mentioned above.

- Ø IT IS REQUIRED TO SUBMIT THE COST OF TENDER DOCUMENTS ALONG WITH TECHNICAL BID AS MENTIONED ABOVE.
- Ø EARNEST MONEY SHOULD BE DEPOSITED IN THE FORM OF ACCOUNT PAYEE DEMAND DRAFT PAYABLE AT SBI, HIRAPUR (CODE-1670) DHANBAD IN FAVOUR OF DIRECTOR, CENTRAL INSTITUTE OF MINING & FUEL RESEARCH, DHANBAD.
- Ø INCOMPLETE TENDERS, LATE / DELAYED TENDERS AS WELL AS TENDERS WITHOUT EARNEST MONEY SHALL BE SUMMARILY REJECTED.
- Ø DIRECTOR, CIMFR, RESERVES THE RIGHT OF ACCEPTING ANY TENDER IN PART OR FULL OR REJECTING ALL WITHOUT ASSIGNING ANY REASON.
- Ø LOWEST QUOTING FIRM HAS TO BE SUBMITTED PERFORMANCE GUARANTEE AS PER RULE BEFORE AWARDING THE JOB.
- Ø ESTIMATE BASED ON DSR-2007 & Local market.

DCI MFR may kindly approve for press, advertisement through the following agency in approved rate DAVP as applicable to Govt. Deptt.

1. The Telegraph, Kolkata Publication (English daily)
2. Times of India, New Delhi
3. Hindustan, Dhanbad Edition (Hindi Local) - Pointer advertisement

Name of Media - M/s. Union Publicity Bureau,

34B, Ballygunge Gardens, Golpark, Kolkata - 700 019.

Sd/-
Head, Civil

Sd/-
Co-ordinator, Civil

Sd/-
A.O.

D/CIMFR

CENTAL INSTITUTE OF MINING & FUEL RESEARCH, DHANBAD
(Council of Scientific & Industrial Research)

Name of work: Renovation of IT Centre, Security officer room, room no. 26, 36, 46, 65, 76, 81, 86 at Main building, Library, Ventilation division (TF-5), Calibration cell by providing and fixing of false ceiling, aluminium partition, working table.

Sl.	Description of work	Quantity	Unit	Rate (in figure & words)	Amount
1.	Providing and fixing at all height false ceiling including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS : 277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5mm diax40mm long with 6mm dia bolts to the angle hangers of 25x25x0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels 45x15x0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick button wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm diax230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the board with recommended filler, jointing tapes, finisher and two coats of primer suitable for board as per manufactures specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed all complete as per drawing and specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum board conforming to IS: 2095- Part I.	685.00	Sqm		
2.	Providing and laying polished vitrified floor tiles in different sizes of size 60x60 cm to be specified by the manufacture with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades and fixing of vitrified floor tiles with cement based high polymer modified quick-set tiles adhesive (water based) conforming to IS: 15477, 5kg adhesive per Sqm of tile area in all 3 mm thickness.	102.00	Sqm		

3.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and paneling to be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15).	850.00	Kg		
4.	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	5.00	Cum		
5.	12 mm thick cement plaster in cm 1:4 (1 cement : 4 fine sand)	41.00	Sqm		
6.	Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side.	250.00	Sqm		
7.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) : With float glass panes of 4.0 mm thickness.	85.00	Sqm		
8.	Providing and fixing flat pressed 3 layer particle board medium density exterior grade –I or graded wood particle board IS : 3087 marked to frame backing or studing with screws etc completework.				
a)	12 mm thick	250.00	Sqm		
b)	18 mm thick	150.00	Sqm		
9.	Providing and fixing 25 mm thick shutters for cupboards etc. including ISI marked black enamelled M.S. butt hinges with necessary screws: Second class teak wood	150.00	Sqm		

10.	Labour charge and carpenter charge for dismantling of wooden and ply board of partition structure including stacking of serviceable material near side and same material by making of working table and cupboard shutter work and providing and fixing of marked block enameled M.S. butt hinges with necessary screws etc. complete work.	60.00	Sqm		
11.	Providing and fixing plywood 4 mm thick one side decorative veneer conforming to IS: 1328 (type-1) for plain lining / cladding with necessary screws, priming coat on unexposed surface with: Decorative veneer facings of approved manufacture.	225.00	Sqm		
12.	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : 75 mm	120 nos.	Each		
13.	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 100x10 mm	120 nos.	Each		
14.	Providing and fixing bright finished brass 100 mm martic latch and lock with 6 levers and a pair of lever handles with necessary screws etc. complete work quality, approved by Civil in-charge including wardrobe knob with necessary screws (best make of approved quality) etc. complete :	120 nos.	Each		
15.	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	1750.00	Sqm		
16.	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats).	1750.00	Sqm		
17.	Applying one coat of cement primer of approved brand and manufacture on wall surface : Cement primer.	1750.00	Sqm		
18.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	625.00	Sqm		
19.	Providing and applying plaster of paris putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete.	175.00	Sqm		
20.	Providing & fixing homogeneous Polyvinyl chloride sheet / tile in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality and manufacturer like Dunlop S-758, Fevicol SR 998 or equivalent including rolling with light wooden roller weighing about 5 kg. all complete as direct ed by Engineer-in-charge, in approved colour and shade.	475.00	Sqm		

21.	Providing and fixing 4 mm thick plywood plain lining with necessary screws, priming coat on unexposed surface etc. complete with : Teak ply facings of approved manufacture.	75.00	Sqm		
22.	Providing and fixing 15 cm high drawer of the cupboard with 12mm thick base and side planks with wooden handle and 20x25mm runners fixed with screws complete including painting or polishing. Note : Overall plan area of the drawer shall be measured. Second class kail wood	65.00	Sqm		
Total (Rs.)					

Signature of Contractor

