

Corrigendum

1. In the 'list of equipment' of NIT Sl. No. 15, 'Flanges', Class 450 rating to be replaced by rating as per design.
2. The word 'provisions' to be replaced by 'to be supplied' in NIT.
3. Design pressure after compressor will be 50 kg/ sqcm (guage). Before gas storage tank it is 1 kg/sqcm(guage)
4. The size of the raw coal to be provided to the vendors will be (-) 200 mm. Successful bidder will have to make arrangement for suitable sizing the coal to be fed to the gasifier.
5. Finished ground will be provided by CIMFR for the Pilot Plant. Load bearing capacity data of the soil for the site provided for the pilot plant will be supplied by CIMFR.
6. Minimum capacity of the gasifier will be 50 kh/h coal.
7. 4 weeks extension for submission of the Bid.
8. Total Project i.e successful commissioning and handing over of the plant should be completed within 15 months.
9. Water and electricity required during fabrication of Pilot plant will be chargeable. Water charges will be @1% of the cost of total Civil Work and electricity charge will be as per actual basis.
10. For goods manufactured outside India, the Supplier shall be entirely responsible for all taxes, stamp duties, license fees, and other such levies imposed outside India. For goods manufactured within India, the supplier shall be entirely responsible for all taxes, duties, license fees, etc, incurred till its final manufacture/production. If any tax exemptions, reductions, allowances or privileges may be available to the supplier in India, the Purchaser shall make its best efforts to enable the supplier to benefit from any such tax savings to the maximum allowable extent.

PAYMENT TERMS

1. 40% of the order value may be paid as advance against Bank Guarantee of equivalent amount.
2. 30% of the order value may be paid after delivery of the full material of the CTL Pilot Plant at CIMFR (Digwadih Campus). Initial B.G will be released after delivery of complete materials.

3. Rest 30% will be paid after successful erection, installation, commissioning, demonstration, training and handling over the Plant against 10% performance Bank Guarantee (PBG).



**Central Institute of Mining & Fuel Research
(CSIR, Ministry of Science & Technology, Govt. of India)**

HQ, Barwa Road Campus, Dhanbad- 8260015

NIT No: CIMFR/PUR/14(1)2010

Dated:-27.08.2010

File No: 13(2)/CIMFR/DE/18/10-11/PUR

CORRIGENDUM

Name of Items:- Design, development, fabrication, installation and commissioning of the Pilot Plant for Coal-to-Liquid Process Development.

Last date of submission : 27.09.2010 up to 3.00 P.M.

Date of Opening : 28.09.2010 at 11.00 A.M

Interested firms may visit our Website: www.cimfr.nic.in for details.

Fax No -0326-2296030/2381210

Stores & Purchase Officer